go P. 20

App. F. IX-4

*Previous References.* 1940-1 ( War ) War File No. 121-40
Serial Nos. 1 to 5

*Later References.*

# GENERAL AND REVENUE SECRETARIAT.

*Serial Nos.* Five only

**Part B for** October 1941

**SUBJECT.**

Supplying power temporarily to the Speech Amplifying Set at the Olympic and Military Sports Ground at Doddakere Maidan, Mysore.

G.O. No W 918-21 dated 23rd Oct '41.

To

The Genl. Supdt., C.P.S.
" Comptroller to Govt.
" Audits, Elect. Dept.
" President, City Mpl. Cl., Mysore.

Sanctions an expenditure of Rs. 142/

25.x.41

W 121-40-1

64R/W

Telephone No. 2110.

IN REPLY REFER TO NO C.5.89-91 ENCLO.

Telegraphic Address:
"GOMED"

CODES USED
BENTLEY'S LIEBER'S
A. B. C. 6th EDITION
BUSINESS TELEGRAPHIC CODE

**GOVERNMENT OF MYSORE**
ELECTRICAL DEPARTMENT

OFFICE OF THE CHIEF ELECTRICAL ENGINEER,
(Camp) Mysore
Bangalore, 1st October 1941.
(MYSORE, S. INDIA.)

To

CHIEF SECRETARY * 1 OCT. 1941 * GOVT OF MYSORE

The Chief Secretary to the Government
of His Highness the Maharaja of Mysore,
Camp Mysore.

Sir,

Supplying power temporarily to the Speech Amplifying set at the Olympic and Military Sports Ground at Doddakere Maidan, Mysore.

---

I have the honour to state that the Superintendent, Mysore Power and Lighting, reports that you have given him personal instructions to instal a Speech Amplifying Apparatus at the above place, pending sanction to the estimate to be forwarded by him to the President, Mysore City Municipality. In accordance therewith the work is being carried out and I request you to kindly confirm this to enable the Auditor, Electrical Department, to admit the expenditure incurred thereon.

Subd with a draft for approval or Mr Adv.

I have the honour to be,
Sir,
Your most obedient servant,

General Superintendent, 1/X
Cauvery Power Scheme.

RS 2/+

Draft for Consideration
(The estimate is to be sent to President, M.C.M.
MH-CSC.
Instructions are necessary re: source from which cost is to be met)
The memo to Auditor may pass through Mr Fin Depr also

CJL 2/10

Chief Sy

648/W

Serial No.

DEWAN'S OFFICE
NO. 2880

FINANCIAL SE - 1941
U.O.N.C. Fl. 1984
4. OCT. 1941

CHIEF SECRETARY
8. OCT. 1941
GOVT. OF MYSORE.

Whilst permission was sought for and given for the Land Speaker arrangements in connection with the Court function, a bar fell at which the Dewan and Law ministers had to preside. Sir Charles requested that this facility may be arranged for. The cost is estimated at Rs 142 and may be met from the Head - Genl Admn.

MMS
2/10/41

Dewan
This file Sir

AS
4.10.41

MMS
5/10/41

MMS
6/10/41

A sentence may perhaps be added in the draft that the cost ~~with~~ may be debited to 12 General Admn

CJB
7/10

Chief Sy

No objn.
MMS
8/10/41

Copy may be sent to President M.C.

CJB
as

Issued No 843/W dy 9.X.41 to the Genl Supdt, C.P.S.
- memo 844/W to the Auditor, Elect. Dept
Subd with a draft ltr for Pres. dt. M.C.?

RS
X/X

CJB
10/10

Issued No 858/W. dy 10.10.41 to the President, M. nopl. Cl

TH2/W.

File No. of 194 | General and Revenue Secretariat

Serial No.

From

The Govt. Supdt. C.P.S.

Letter no 8243 d 20.11 subm. 4 fwd estimate for Rs 142/- for sanction Govt under 12 Govt. Admr

The Govt. Supdt was already intimated that the expenditure may be debited to 12 Govt. Admr and a copy was sent to Auditor Elect. Supdt. Subd with a draft G.O sanctioning the estimate for approval or other orders.

RS 23/X

22/11

Appendix F G—1]

SUBJECT.....

.....

.....

Section W

File No. 121-40

Serial No. 2

*Diary No. of letter replied to*.....

No. 843/W

To

Genl. Inspr. Infantry.
Convy Forts Scheme.

General and Revenue Secretariat

( )

*the* *19*

Supplying power temporarily to the Speech amplifying Set at the Olympic and Military Sports Ground at Dodballapur Maidan. Mysore.

Date of issue 9.10.41

Sir,

Signed by Mr. C. Ly. R.

With reference to your letter No C.589-91 dt 1st Octr. 41 on the above subject. I am directed to confirm the personal instruction given by me to the Supdt. M.P.L. to install a Speech Amplifying Apparatus at the Dodballapur Maidan.

List of enclosures ~~to the~~ pending sanction estimate to be forwarded by him to the President

A copy of this letter has been sent to the Accountant, Electrical Dept. so as to enable him to admit

Copied by ~~to~~ M.C.M.

Examined by .....

the expenditure incurred thereon.

I have the

11/5/2010

Chief Secretary to Govt

Copy to the Executive Health Deptt
with a copy of the Report & bills

GOVERNMENT OF HIS HIGHNESS THE MAHARAJA OF MYSORE

General and Revenue Secretariat

Camp: Mysore,
Bangalore, Dated, 7th October 1941.

No.

From

*Rajasevaprasaktha*
B. T. KESAVAIENGAR, Esq., B.A.,
*Chief Secretary to the Government of His Highness the Maharaja of Mysore.*

To

General Superintendent,
Cauvery Power Scheme.

Sir,

Supplying power temporarily to the speech amplifying set at the Olympic and Military Sports ground at Doddakere Maidan, Mysore.

- - - -

With reference to your letter No.C.589-91 dated the 1st October 1941 on the above subject, I am directed to confirm the personal instructions given by me to the Superintendent, Mysore Power and Lighting, to instal a speech amplifying apparatus at the Doddakere Maidan pending sanction to the estimate to be forwarded by him to the President, Mysore City Municipality. A copy of this letter has been sent to the Auditor Electrical Department, so as to enable him to admit the expenditure incurred therein.

The expre on this account may be debited to "12 Genl Admn"

I have the honour to be,

Sir,

Your most obedient servant,

(Sd.) B.T. Kesavaiengar.

Chief Secretary to Government.

Memo No. Dated the 7th October 1941.

Copy of the above is forwarded to the Auditor, Electrical Department with a copy of the Superintendent's letter dated the 1st Octr.19

For Chief Secretary to Government

Camp: Mysore,
xxxxxxx 9th October 1941.

No. 843/W

W 121-40-2

The General Superintendent,
Cauvery Power Scheme.

Supplying power temporarily to the speech amplifying set at the Olympic and Military Sports ground at Doddakere Maidan, Mysore.

- - - -

With reference to your letter No.7.589-91 dated the 1st October 1941 on the above subject, I am directed to confirm the personal instructions given by me to the Superintendent, Mysore Power and Lighting, to instal a speech amplifying apparatus at the Doddakere Maidan pending sanction to the estimate to be forwarded by him to the President, Mysore City Municipality. The expenditure on this account may be debited to "12 General Administration".

A copy of this letter has been sent to the Auditor, Electrical Department, so as to enable him to admit the expenditure incurred therein.

I have the honour to be,
Sir,
Your most obedient servant,

(Sd.) B.T. Kesavaiengar.

Chief Secretary to Government.

Memo No. 844/W. Dated the 9th October 1941.

Copy of the above is forwarded to the Auditor, Electrical Department with a copy of the Superintendent's letter dated the 1st Octr.1941. Encl

For Chief Secretary to Government.

W121-40-3

No. 858/W
Enc 1

Camp: Mysore,
xxxxxxx 10th October 1941.

The President,
City Municipal Council,
Mysore.

Supplying power temporarily to the Speech Amplifying set at the Olympic and Military Sports Ground at Doddakere Maidan, Mysore.

- - - - - -

I am directed to enclose herein for your information a cop of letter No.C.589-91 dated the 1st October 1941 received from the General Superintendent, Cauvery Power Scheme, and of this office reply thereto, on the above subject.

I have the honour to be,

Sir,

Your most obedient servant,

For Chief Secretary to Government.

W 121-40-4.

742/W

Telephone No. 2110

IN REPLY REFER TO
No. 8243.
ENCLS. 2 {Estimate in triplicate / Report in duplicate

Telegraphic Address:
"GOMED"

CODES USED
BENTLEY'S LIEBER'S
A. B. C. 6TH EDITION
BUSINESS TELEGRAPH CODE.

**GOVERNMENT OF MYSORE**
**ELECTRICAL DEPARTMENT.**

OFFICE OF THE GENERAL SUPERINTENDENT,
CAUVERY POWER SCHEME,
*Bangalore,* 20th October 1941.
(MYSORE, S. INDIA.)

*From*

CHIEF SECRETARY. 22. OCT. 1941 GOVT. OF MYSORE.

M. HAYATH, ESQ., B.E., (MECH.), B.S.E.E.,
GENERAL SUPERINTENDENT,
CAUVERY POWER SCHEME,
BANGALORE.

The Chief Secretary to the
Government of His Highness the
Maharaja of Mysore, Bangalore.

Sir,

Subject:- Supplying power temporarily to the speech amplifying set at the Olympic and Military Sports Ground at Doddakere Maidan, Mysore.

K With reference to correspondence ending with your letter No.843/W dated 9-10-1941, I have the honour to forward herewith an estimate amounting to Rs142/- for obtaining sanction of Government thereto. under "12 General Administration".

2. The report accompanying the estimate explains the provisions made therein.

I have the honour to be,
Sir,
Your most obedient servant,

M. Hayath
General Superintendent,
Cauvery Power Scheme.

MRA-CA-AK.

Government of Mysore. Electrical Department.

Report to accompany the estimate for supplying power to temporary speech amplifying set and loud speakers for - Olympic Sports at Doddakere Maidan, Mysore.

---

Reference:- As per personal requisition of the Chief Secretary to the Government of Mysore.

---

It is proposed to erect 8 poles and to run 8 spans of 60 cycle 220 volt secondaries from the proposed transformer centre of 1 of 3 KVA which will be mounted on the existing 4 pole structure tapping from No.1 Incandescent circuit. Further loud speaker circuit will be run by 7 spans by using 4 poles and No.10 B.&.S.copper wire as shown in the accompanying sketch. The above transformer of 3 KVA will take care of the load and other necessary materials with labour are provided in this estimate for carrying out the work, including dismantling after the function is over.

The period of service required is assumed to be one month only.

All the returnable materials have been credited in the estimate and the work is proposed to be carried out - departmentally. All the materials proposed in the estimate are available in stock at the rates mentioned ~~in the estim~~ therein.

---

KAV/CNR.

H. Ramarao
Superintendent, M.P.L.

M R Ayyangar
for General Superintendent,
C.P.S. 20/10

G. R. S. App. F VI—G 2]

SUBJECT .....

.....

.....

*Diary. No. of letter replied to*.....

Section W

File No. 121 - 40

Serial No. 5

General and Revenue Secretariat

( )

*the* *193*

*Proceedings of the Government of His Highness the Maharaja of Mysore.*

Date of issue 23. 10. 1941.

Signed by Mr. S. K. V. Iyer

*Read*— Letter no 8243 d 20th Oct. 41 from the Supdt. C.P.S forwarding an estimate amounting to Rs 142/- for supplying power temporarily to the speech amplifying set at the Olympic and Military Sports Ground at Doddakere Maidan, Mysore

~~Order thereon.—No.~~

duly to Dasara and requesting sanction of Govt thereto, under 12 Govt. Advr.

Govt:- 918-21/W

Sanctioned. The expenditure being debited to 12 Govt. Advr.

for Secretary to Government

May this be—

(i) printed?

(ii) treated as a standing order?

(iii) published in the Gazette, English Part?

(iv) translated?

(v) placed at the disposal of the press?

(vi) published in the Gazette, Kannada Part?

(1) Govt. Supdt. C.P.S.
(2) Comptr to Govt
(3) Assistant. Elect. Dept
(4) President. City Municipal Council Mysore

Chief Secretary to Government

PROCEEDINGS OF THE GOVERNMENT OF HIS HIGHNESS
THE MAHARAJA OF MYSORE.

Read:—

Letter No.8243 dated the 20th October 1941 from the General Superintendent, Cauvery Power Scheme, forwarding an estimate amounting to Rs.142/- for supplying power temporarily to the speech amplifying set at the Olympic and Military Sports Ground at Doddakere Maidan, Mysore, during the Dasara and requesting sanction of Government thereto, under 12 General Administration.

- - - - -

ORDER NO. W 918-21/W 121-40-5

Dated, Bangalore, the 23rd October 1941.

Sanctioned, the expenditure being debited to 12 General Administration.

For Chief Secretary to Government.

To

The General Superintendent, Cauvery Power Scheme.
The Comptroller to Government.
The Auditor, Electrical Department.
The President, City Municipal Council, Mysore.

PROCEEDINGS OF THE GOVERNMENT OF HIS HIGHNESS
THE MAHARAJA OF MYSORE.

Read:—

Letter No.8243 dated the 20th October 1941 from the General Superintendent, Cauvery Power Scheme, forwarding an estimate amounting to Rs.142/- for supplying power temporarily to the speech amplifying set at the Olympic and Military Sports Ground at Doddakere Maidan, Mysore, during the Dasara and requesting sanction of Government thereto, under 12 General Administration.

- - - - -

ORDER NO. W 918-21/W 121-40-5

Dated, Bangalore, the 23rd October 1941.

Sanctioned, the expenditure being debited to 12 General Administration.

For Chief Secretary to Government.

To

The General Superintendent, Cauvery Power Scheme.
The Comptroller to Government.
The Auditor, Electrical Department.
The President, City Municipal Council, Mysore.

Government of Mysore. Electrical Department.

Report to accompany the estimate for supplying power to temporary speech amplifying set and loud speakers for - Olympic Sports at Doddakere Maidan, Mysore.

---

Reference:- As per personal requisition of the Chief Secretary to the Government of Mysore.

---

It is proposed to erect 8 poles and to run 8 spans of 60 cycle 220 volt secondaries from the proposed transformer centre of 1 of 3 KVA which will be mounted on the existing 4 pole structure tapping from No.1 Incandescent circuit. Further loud speaker circuit will be run by 7 spans by using 4 poles and No.10 B.&.S.copper wire as shown in the accompanying sketch. The above transformer of 3 KVA will take care of the load and other necessary materials with labour are provided in this estimate for carrying out the work, including dismantling after the function is over.

The period of service required is assumed to be one month only.

All the returnable materials have been credited in the estimate and the work is proposed to be carried out - departmentally. All the materials proposed in the estimate are available in stock at the rates mentioned ~~in the estimate~~ therein.

---

KAV/CNR.

K. Ramaiah
Superintendent, M&P.L.

M.V. Ayyangar
General Superintendent,
C.P.S. 20/10

GOVERNMENT OF MYSORE. ELECTRICAL DEPARTMENT.

Estimate of the probable cost of supplying power to temporary Speach Amplifying Set at the Olympic Sports Grounds at Doddakere Maidan, Mysore.

| Sl. No. | Names of materials Etc. | Unit. | Quantity. | Rate. | Amount. |
|---|---|---|---|---|---|
| 1. | Poles corroded 24 ft. to 26 ft.long. | No. | 8/205 | 0 3 0 | 38 7 0 |
| 2. | Wooden pole 26 ft. long. | " | 1 | Rs.12/- | 12 0 0 |
| 3. | S.M.Rail 24 ft.long 41½ lbs.Section. | " | 3 | 8 4 0 | 24 12 0 |
| 4. | Cross arm 3kpin S.C.A. for No.2 pole complete. | " | 27 | 1 10 1 | 44 0 0 |
| 5. | Cross arm 3kpin S.C.A. for M-Pole. | " | 3 | 1 12 0 | 5 4 0 |
| 6. | Insulators and pins for D.L. | " | 48 | 1 0 2 | 48 8 0 |
| 7. | Strain insulators for 13 K.V. | " | 4 | 0 14 6 | 3 10 0 |
| 8. | Guy sets complete. | Sets | 2 | 4 9 6 | 9 3 0 |
| 9. | Wire copper No.6 B&S bare | Lbs. | 344 | 0 9 2 | 197 1 0 |
| 10. | Wire copper No.10 B&S bare. | Lbs. | 167 | 0 5 5 | 56 9 0 |
| 11. | Transformer 3 K.V.A.single voltage with hooks. | No. | 1 | - | 231 2 0 |
| 12. | Transil oil No.10-C. | Gln. | 5 | 1 6 10 | 7 2 0 |
| 13. | Frame for hoisting on M-pole. | Set | 1 | 2 0 0 | 2 0 0 |
| 14. | Lightning Arrestors 3 to 6 K.V. | No. | 2 | 29 2 0 | 58 4 0 |
| 15. | Wire copper No.8 B&S bare out of scrap copper. | Lbs. Rft. | 2½ 50 | 0 3 0 per lb. | 0 8 0 |
| 16. | Wire insulated No.10 L.T. | Rft. | 100 | 0 1 1 | 6 12 0 |
| 17. | C.I.Box small with F & B holders complete to go on No.2 pole. | No. | 1 | | 1 12 0 |
| 18. | Sundries such as acme tape etc. | | | L.S. | 3 0 0 |
| 19. | Cart hire to and fro | | | " | 10 0 0 |
| 20. | Labour charges for erecting poles, stringing copper wire, hoisting transformer etc., and dismantling the same. | | | " | 104 8 0 |
| | | Total | | | Rs.864 6 0 |

C R E D I T S.

| | | | | | |
|---|---|---|---|---|---|
| 1. | Poles corroded 24 ft.to 26' long. | No. | 8/205 | 0 3 0 | 38 7 0 100 % |
| 2. | Wooden pole 26 ft. long. | " | 1 | - | 12 0 0 " |
| 3. | S.M.Rail 24' long 41½ lbs.Section. | " | 3 | 8 4 0 | 24 12 0 " |
| 4. | Cross arm 3kpin S.C.A. for No.2 pole | " | 27 | 1 10 1 | 44 0 0 " |

| | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 5. | Cross arm 3 pin S.C.A.for M-pole. | No. | 3 | 1 | 12 | 0 | 119-3-0 5 | 4 | 0 | / | 100% |
| 6. | Insulators & pins for D.L. | " | 48 | 1 | 0 | 2 | 48 | 8 | 0 | / | " |
| 7. | Strain insulators ~~xxx~~ for 13.2 K.V. | | 4 | 0 | 14 | 6 | 3 | 10 | 0 | / | " |
| 8. | Guy sets complete. | " | 2 | 4 | 9 | 6 | 9 | 3 | 0 | / | " |
| 9. | Wire copper No.6 B&S bare. | Lbs. | 344 | 0 | 9 | 2 | 197 | 1 | 0 | / | " |
| 10. | Wire copper No.10 B&S bare | " | 167 | 0 | 5 | 5 | 56 | 9 | 0 | / | " |
| 11. | Transformer 3 K.V.A. single voltage with hooks. | No. | 1 | | - | | 231 | 2 | 0 | / | " |
| 12. | Transil oil No.10-C. | Gln. | 5 | 1 | 6 | 10 | 7 | 2 | 0 | / | " |
| 13. | Frame for hoisting on M-poles. | Set | 1 | 2 | 0 | 0 | 2 | 0 | 0 | / | " |
| 14. | Lightning arresters 3 to 6 K.V. | No. | 2 | 29 | 2 | 0 | 58 | 4 | 0 | / | " |
| 15. | Wire insulated No.10 L.T. | Rft. | 90 | 0 | 1 | 1 | 6 | 1 | 0 | / | " |
| 16. | C.I.Box small with F.L.B. holders complete to go on No.2 pole. | No. | 1 | | - | | 1 | 12 | 0 | / | " |
| 17. | Copper scrap. | Lbs. | 2½ | 0 | 3 | 0 | 0 | 8 | 0 | / | " |
| | | | | | | | 119 | | | | |
| | | | | Total Credits | | .. | Rs. | 746 | 3 | 0 | / |

## A B S T R A C T.

| | | |
|---|---|---|
| Total of Estimate | .. | Rs.864 6 0/ |
| -do- credits | .. | 746 3 0/ |
| Net amount of estimate | | Rs118 3 0/ |
| Depreciation at 2%per month | | 14 14 0/ |
| Stock Incidental at 10% on store materials | | 1 14 0/ |
| Contingencies at 5% + 2½% on under pole | | 6 12 0/ |
| T o t a l | | Rs.141 11 0/ |
| | or say | Rs.142 0 0/ |

Rupees One Hundred and Forty-two only.

---

Certified that I have personally visited the spot and prepared the estimate using to-days ledger rates and provided for the most economical and safe way of executing the work.

Sd/- M.Ramamurthy.

KAV-SJG.

16.1.41
Superintendent, T.P.& L.

General ~~Superintendent~~,
C.P.S. 20/1

GOVERNMENT OF MYSORE. ELECTRICAL DEPARTMENT.

Estimate of the probable cost of supplying power to temporary Speach Amplifying Set at the Olympic Sports Grounds at Doddakere Maidan, Mysore.

| Sl. No. | Names of materials Etc. | Unit. | Quantity. | Rate. | Amount. |
|---|---|---|---|---|---|
| 1. | Poles corroded 24 ft. to 26 ft.long. | No. | 8/205 | 0 3 0 | 38 7 0 |
| 2. | Wooden pole 26 ft. long. | " | 1 | Rs.12/- | 12 0 0 |
| 3. | S.M.Rail 24 ft.long 41¼ lbs.Section. | " | 3 | 8 4 0 | 24 12 0 |
| 4. | Cross arm 3 pin S.C.A. for No.2 pole complete. | " | 27 | 1 10 1 | 44 0 0 |
| 5. | Cross arm 3 pin S.C.A. for M-Pole. | " | 3 | 1 12 0 | 5 4 0 |
| 6. | Insulators and pins for D.L. | " | 48 | 1 0 2 | 48 8 0 |
| 7. | Strain insulators for 13 K.V. | " | 4 | 0 14 6 | 3 10 0 |
| 8. | Guy sets complete. | Sets | 2 | 4 9 6 | 9 3 0 |
| 9. | Wire copper No.6 B&S bare | Lbs. | 344 | 0 9 2 | 197 1 0 |
| 10. | Wire copper No.10 B&S bare. | Lbs. | 167 | 0 5 5 | 56 9 0 |
| 11. | Transformer 3 K.V.A.single voltage with hooks. | No. | 1 | - | 231 2 0 |
| 12. | Transil oil No.10-C. | Gln. | 5 | 1 6 10 | 7 2 0 |
| 13. | Frame for hoisting on M-pole. | Set | 1 | 2 0 0 | 2 0 0 |
| 14. | Lightning Arrestors 3 to 6 K.V. | No. | 2 | 29 2 0 | 58 4 0 |
| 15. | Wire copper No.8 B&S bare out of scrap copper. | Lbs.<br>Rft. | 2½<br>50 | 0 3 0<br>per lb. | 0 8 0 |
| 16. | Wire insulated No.10 L.T. | Rft. | 100 | 0 1 1 | 6 12 0 |
| 17. | C.I.Box small with F & B holders complete to go on No.2 pole. | No. | 1 | | 1 12 0 |
| 18. | Sundries such as acme tape etc. | | | L.S. | 3 0 0 |
| 19. | Cart hire to and fro | | | " | 10 0 0 |
| 20. | Labour charges for erecting poles, stringing copper wire, hoisting transformer etc., and dismantling the same. | | | " | 104 8 0 |
| | | T o t a l | | | Rs.864 6 0 |

C R E D I T S.

| | | | | | | |
|---|---|---|---|---|---|---|
| 1. | Poles corroded 24 ft.to 26' long. | No. | 8/205 | 0 3 0 | 38 7 0 | 10% |
| 2. | Wooden pole 26 ft. long. | " | 1 | - | 12 0 0 | " |
| 3. | S.M.Rail 24' long 41¼ lbs.Section. | " | 3 | 8 4 0 | 24 12 0 | " |
| 4. | Cross arm 3 pin S.C.A. for No.2 pole | " | 27 | 1 10 1 | 44 0 0 | " |

| | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| 5. | Cross arm 3 pin S.C.A.for M-pole. | No. | 3 | 1 | 12 | 0 | 5 | 4 | 0 | 100% |
| 6. | Insulators & pins for D.L. | " | 48 | 1 | 0 | 2 | 48 | 8 | 0 | " |
| 7. | Strain insulators ~~xxx~~ for 13.2 K.V. | | 4 | 0 | 14 | 6 | 3 | 10 | 0 | " |
| 8. | Guy sets complete. | " | 2 | 4 | 9 | 6 | 9 | 3 | 0 | " |
| 9. | Wire copper No.6 B&S bare. | Lbs. | 344 | 0 | 9 | 2 | 197 | 1 | 0 | " |
| 10. | Wire copper No.10 B&S bare | " | 167 | 0 | 5 | 5 | 56 | 9 | 0 | " |
| 11. | Transformer 3 K.V.A. single voltage with hooks. | No. | 1 | | - | | 231 | 2 | 0 | " |
| 12. | Transil oil No.10-C. | Gln. | 5 | 1 | 6 | 10 | 7 | 2 | 0 | " |
| 13. | Frame for hoisting on M-poles. | Set | 1 | 2 | 0 | 0 | 2 | 0 | 0 | " |
| 14. | Lightning arresters 3 to 6 K.V. | No. | 2 | 29 | 2 | 0 | 58 | 4 | 0 | " |
| 15. | Wire insulated No.10 L.T. | Rft. | 90 | 0 | 1 | 1 | 6 | 1 | 0 | " |
| 16. | C.I.Box small with F.L.B. holders complete to go on No.2 pole. | No. | 1 | | - | | 1 | 12 | 0 | " |
| 17. | Copper scrap. | Lbs. | 2½ | 0 | 3 | 0 | 0 | 8 | 0 | " |
| | | | | | | Total Credits .. | Rs.746 | 3 | 0 | |

## A B S T R A C T.

| | | |
|---|---|---|
| Total of Estimate .. | | Rs.864 6 0 |
| -do- credits .. | | 746 3 0 |
| Net amount of estimate | | Rs118 3 0 |
| Depreciation at 2%per month | | 14 14 0 |
| Stock Incidental at 10% on other material + 2½% on brass fittings | | 1 14 0 |
| Contingencies at 5% | | 6 12 0 |
| T o t a l | | Rs.141 11 0 |
| | or say | Rs.142 0 0 |

Rupees One Hundred and Forty-two only.

---

Certified that I inspected the spot personally and prepared the estimate using to-day's ledger rates and provided for the most economical and safe way of executing the work.

Sd/- M.Ramamurthy.

KAV-SJG.

16.2.1940
Superintendent, M.P.& L.

~~General Superintendent,~~
C.P.S. 20/6

GOVERNMENT OF MYSORE. ELECTRICAL DEPARTMENT.

Estimate of the probable cost of supplying power to temporary Speach Amplifying Set at the Olympic Sports Grounds at Doddakere Maidan, Mysore.

| Sl. No. | Names of materials Etc. | Unit. | Quantity. | Rate. | Amount. |
|---|---|---|---|---|---|
| 1. | Poles corroded 24 ft. to 26 ft.long. | No. | 8/205 | 0 3 0 | 38 7 0 |
| 2. | Wooden pole 26 ft. long. | " | 1 | Rs.12/- | 12 0 0 |
| 3. | S.M.Rail 24 ft.long 41¼ lbs.Section. | " | 3 | 8 4 0 | 24 12 0 |
| 4. | Cross arm 3 pin S.C.A. for No.2 pole complete. | " | 27 | 1 10 1 | 44 0 0 |
| 5. | Cross arm 3kpin S.C.A. for M-Pole. | " | 3 | 1 12 0 | 5 4 0 |
| 6. | Insulators and pins for D.L. | " | 48 | 1 0 2 | 48 8 0 |
| 7. | Strain insulators for 13 K.V. | " | 4 | 0 14 6 | 3 10 0 |
| 8. | Guy sets complete. | Sets | 2 | 4 9 6 | 9 3 0 |
| 9. | Wire copper No.6 B&S bare | Lbs. | 344 | 0 9 2 | 197 1 0 |
| 10. | Wire copper No.10 B&S bare. | Lbs. | 167 | 0 5 5 | 56 9 0 |
| 11. | Transformer 3 K.V.A.single voltage with hooks. | No. | 1 | - | 231 2 0 |
| 12. | Transil oil No.10-C. | Gln. | 5 | 1 6 10 | 7 2 0 |
| 13. | Frame for hoisting on M-pole. | Set | 1 | 2 0 0 | 2 0 0 |
| 14. | Lightning Arrestors 3 to 6 K.V. | No. | 2 | 29 2 0 | 58 4 0 |
| 15. | Wire copper No.8 B&S bare out of scrap copper. | Lbs. Rft. | 2½ 50 | 0 3 0 per lb. | 0 8 0 |
| 16. | Wire insulated No.10 L.T. | Rft. | 100 | 0 1 1 | 6 12 0 |
| 17. | C.I.Box small with F & B holders complete to go on No.2 pole. | No. | 1 | | 1 12 0 |
| 18. | Sundries such as acme tape etc. | | | L.S. | 3 0 0 |
| 19. | Cart hire to and fro | | | " | 10 0 0 |
| 20. | Labour charges for erecting poles, stringing copper wire, hoisting transformer etc., and dismantling the same. | | | " | 104 8 0 |
| | | T o t a l | | | Rs.864 6 0 |

C R E D I T S.

| | | | | | | |
|---|---|---|---|---|---|---|
| 1. | Poles corroded 24 ft.to 26' long. | No. | 8/205 | 0 3 0 | 38 7 0 | 10% |
| 2. | Wooden pole 26 ft. long. | " | 1 | - | 12 0 0 | " |
| 3. | S.M.Rail 24' long 41¼ lbs.Section. | " | 3 | 8 4 0 | 24 12 0 | " |
| 4. | Cross arm 3kpin S.C.A. for No.2 pole | " | 27 | 1 10 1 | 44 0 0 | " |

| | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| 5. | Cross arm 3 pin S.C.A.for M-pole. | No. | 3 | 1 | 12 | 0 | 5 | 4 | 0 | 100% |
| 6. | Insulators & pins for D.L. | | 48 | 1 | 0 | 2 | 48 | 8 | 0 | " |
| 7. | Strain insulators xix for 13.2 K.V. | | 4 | 0 | 14 | 6 | 3 | 10 | 0 | " |
| 8. | Guy sets complete. | | 2 | 4 | 9 | 6 | 9 | 3 | 0 | " |
| 9. | Wire cooper No.6 B&S bare. | Lbs. | 344 | 0 | 9 | 2 | 197 | 1 | 0 | " |
| 10. | Wire copper No.10 B&S bare | | 167 | 0 | 5 | 5 | 56 | 9 | 0 | " |
| 11. | Transformer 3 K.V.A. single voltage with hooks. | No. | 1 | | - | | 231 | 2 | 0 | " |
| 12. | Transil oil No.10-C. | Gln. | 5 | 1 | 6 | 10 | 7 | 2 | 0 | " |
| 13. | Frame for roisting on M-poles. | Set | 1 | 2 | 0 | 0 | 2 | 0 | 0 | " |
| 14. | Lightning arresters 3 to 6 K.V. | No. | 2 | 29 | 2 | 0 | 58 | 4 | 0 | " |
| 15. | Wire insulated No.10 L.T. | Rft. | 90 | 0 | 1 | 1 | 6 | 1 | 0 | " |
| 16. | C.I.Box small with F.L.B. holders complete to go on No.2 pole. | No. | 1 | | - | | 1 | 12 | 0 | " |
| 17. | Copper scrap. | Lbs. | 2½ | 0 | 3 | 0 | 0 | 8 | 0 | " |
| | | | | Total Credits | | .. | Rs.746 | 3 | 0 | |

## A B S T R A C T.

| | | | | |
|---|---|---|---|---|
| Total of Estimate | .. | Rs.864 | 6 | 0 |
| -do- credits | .. | 746 | 3 | 0 |
| Net amount of estimate | | Rs118 | 3 | 0 |
| Depreciation at 2%per month | | 14 | 14 | 0 |
| Stock Incidental at 10% | | 1 | 14 | 0 |
| Contingencies at 5% | | 6 | 12 | 0 |
| T o t a l | | Rs.141 | 11 | 0 |
| | or say | Rs.142 | 0 | 0 |

Rupees One Hundred and Forty-two only.

---

Certified that I inspected the spot personally and prepared the estimate using to-day's ledger rates and provided for the most economical and safe way of executing the work.

Sd/- M.Ramamurthy.

KAV-SJG.

16: Ramadas 11/10
Superintendent, H. & L.

M R Ry
General Superintendent,
C.P.S. 24/10